

SECTION 017117 – ANIMAL MANAGEMENT REQUIREMENTS OF CONSTRUCTION

PART 1 GENERAL

1.1 SCOPE OF WORK

- A. Animal Management requirements of construction are indicated at various areas of the Construction Documents. These requirements are general in nature and indicate universal type details required to be constructed as part of the Base Contract Price for this Project. Inclusive of the requirements, the Contractor, all subcontractors and all sub-subcontractors shall, as part of the Base Contract, do the following:
 - 1. Hide all conduits, pipes, water lines, cables, utility lines, etc. or other loose construction at the minimum distance indicated in the Contract Documents, to avoid animal contact. Where this is not possible, the specified guard plates, or other protective devices shall be installed at no additional cost to the Base Contract Price.
 - 2. Animals have been known to injure themselves due to items left in holding or exhibit spaces during construction. Each contractor is responsible for regularly removing all construction debris in compliance with this requirement for work in his/her area including, but not limited to nails, screws, wire, wood, metal scraps, welding rods, and other small fasteners or miscellaneous items.
 - 3. Provide the special animal management requirements of construction wherever required as shown in the Drawings or written into these Specifications.
- B. The intent of these requirements is to ensure that the Owner obtains a facility in which personnel and animals may interact safely for the betterment of the entire facility. These requirements are not intended to cover all conditions that may arise during construction and the Contractor must cooperate with the Owner, Owner's designated staff, Architect, and Landscape Architect during the construction period.
- C. The General Contractor shall recognize that this facility is of unique construction and shall at all times take precaution to minimize the use of the Animal Management requirements as much as possible by thorough coordination of all the sub-trades involved, and through coordination of placement of all Work prior to installation throughout the Project, to minimize contact with animals on exhibit throughout the Zoo.

PART 2 PRODUCTS

2.1 GENERAL

- A. Provide the materials shown in the drawings and notes where conditions require their respective use. See A or CG series of Drawings for cover plates. Other shapes, not shown, might be required to accomplish the intended goal of animal protection.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Install all required items and/or perform all required work to create uniform and consistent conditions to the requirements of the Animal Management notes and details. This includes small, medium, and large indoor holding spaces and exterior yards.

END OF SECTION 017117